

RE: **PURDUE UNIVERSITY 157-15996-00012**

February 17, 2003

TO: Interested Parties / Applicant

FROM: Paul Dubenetzky
Chief, Permits Branch
Office of Air Quality

Notice of Decision: Approval - Effective Immediately

Please be advised that on behalf of the Commissioner of the Department of Environmental Management, I have issued a decision regarding the enclosed matter. Pursuant to IC 13-17-3-4 and 326 IAC 2, this permit modification is effective immediately, unless a petition for stay of effectiveness is filed and granted, and may be revoked or modified in accordance with the provisions of IC 13-15-7-1.

If you wish to challenge this decision, IC 4-21.5-3-7 require that you file a petition for administrative review. This petition may include a request for stay of effectiveness and must be submitted to the Office of Environmental Adjudication, ISTA Building, 150 W. Market Street, Suite 618, Indianapolis, IN 46204, **within (18) eighteen days of the mailing of this notice**. The filing of a petition for administrative review is complete on the earliest of the following dates that apply to the filing:

- (1) the date the document is delivered to the Office of Environmental Adjudication (OEA);
- (2) the date of the postmark on the envelope containing the document, if the document is mailed to OEA by U.S. mail; or
- (3) the date on which the document is deposited with a private carrier, as shown by receipt issued by the carrier, if the document is sent to the OEA by private carrier.

The petition must include facts demonstrating that you are either the applicant, a person aggrieved or adversely affected by the decision or otherwise entitled to review by law. Please identify the permit, decision, or other order for which you seek review by permit number, name of the applicant, location, date of this notice and all of the following:

- (1) the name and address of the person making the request;
- (2) the interest of the person making the request;
- (3) identification of any persons represented by the person making the request;
- (4) the reasons, with particularity, for the request;
- (5) the issues, with particularity, proposed for consideration at any hearing; and
- (6) identification of the terms and conditions which, in the judgment of the person making the request, would be appropriate in the case in question to satisfy the requirements of the law governing documents of the type issued by the Commissioner.

(over)

PART 70 MINOR SOURCE MODIFICATION OFFICE OF AIR QUALITY

**Purdue University
423 South Grant Street
West Lafayette, Indiana 47907**

(herein known as the Permittee) is hereby authorized to construct and operate subject to the conditions contained herein, the emission units described in Section A (Source Summary) of this approval.

This approval is issued in accordance with 326 IAC 2 and 40 CFR Part 70 Appendix A and contains the conditions and provisions specified in 326 IAC 2-7 as required by 42 U.S.C. 7401, et. seq. (Clean Air Act as amended by the 1990 Clean Air Act Amendments), 40 CFR Part 70.6, IC 13-15 and IC 13-17.

Source Modification No.: 157-15996-00012	
Issued by: Original signed by Paul Dubenetzky, Branch Chief Office of Air Quality	Issuance Date: February 17, 2003

TABLE OF CONTENTS

A SOURCE SUMMARY

- A.1 General Information [326 IAC 2-7-4(c)] [326 IAC 2-7-5(15)]
- A.2 Emission Units and Pollution Control Equipment Summary [326 IAC 2-7-4(c)(3)]
- A.3 Part 70 Permit Applicability [326 IAC 2-7-2]

B GENERAL CONSTRUCTION CONDITIONS

- B.1 Definitions [326 IAC 2-7-1]
- B.2 Effective Date of the Permit [IC13-15-5-3]
- B.3 Revocation of Permits [326 IAC 2-1.1-9(5)][326 IAC 2-7-10.5(i)]

C GENERAL OPERATION CONDITIONS

- C.1 Certification [326 IAC 2-7-4(f)] [326 IAC 2-7-6(1)][326 IAC 2-7-5(3)(C)]
- C.2 Preventive Maintenance Plan [326 IAC 2-7-5(1),(3) and (13)] [326 IAC 2-7-6(1) and (6)]
- C.3 Permit Amendment or Modification [326 IAC 2-7-11] [326 IAC 2-7-12]
- C.4 Opacity [326 IAC 5-1]
- C.5 Fugitive Dust Emissions [326 IAC 6-4]
- C.6 Operation of Equipment [326 IAC 2-7-6(6)]
- C.7 Stack Height [326 IAC 1-7]
- C.8 Performance Testing [326 IAC 3-6][326 IAC 2-1.1-11]
- C.9 Compliance Requirements [326 IAC 2-1.1-11]
- C.10 Compliance Monitoring [326 IAC 2-7-5(3)] [326 IAC 2-7-6(1)]
- C.11 Monitoring Methods [326 IAC 3] [40 CFR 60] [40 CFR 63]
- C.12 Pressure Gauge and Other Instrument Specifications [326 IAC 2-1.1-11]
- C.13 Compliance Response Plan - Preparation, Implementation, Records, and Reports
- C.14 Emergency Provisions
- C.15 Actions Related to Noncompliance Demonstrated by a Stack Test [326 IAC 2-7-5]
- C.16 General Record Keeping Requirements [326 IAC 2-7-5(3)]
- C.17 General Reporting Requirements [326 IAC 2-7-5(3)(C)]

D.1 FACILITY OPERATION CONDITIONS

Dry Ash Loading System

- D.1.1 Particulate Emission Limitations
- D.1.2 Preventative Maintenance Plan
- D.1.3 Fugitive Dust Emissions
- D.1.4 Opacity Limitations
- D.1.5 Particulate Matter
- D.1.6 Visible Emissions Notations
- D.1.7 Parametric Monitoring
- D.1.8 Record Keeping Requirements
- D.1.9 Reporting Requirements

Certification

Permit Reviewer: Walter Habeeb

SECTION A

SOURCE SUMMARY

This approval is based on information requested by the Indiana Department of Environmental Management (IDEM), Office of Air Quality (OAQ). The information describing the emission units contained in conditions A.1 through A.2 is descriptive information and does not constitute enforceable conditions. However, the Permittee should be aware that a physical change or a change in the method of operation that may render this descriptive information obsolete or inaccurate may trigger requirements for the Permittee to obtain additional permits or seek modification of this approval pursuant to 326 IAC 2, or change other applicable requirements presented in the permit application.

A.1 General Information [326 IAC 2-7-4(c)] [326 IAC 2-7-5(15)]

The Permittee owns and operates stationary boilers and ash handling system for the educational services operations located at Purdue University.

Responsible Official:	Wayne W. Kjonaas
Source Address:	423 S. Grant Street, West Lafayette, Indiana 47907
Mailing Address:	401S. Grant Street, 1665 L.J.Freehafer Hall of Administrative Services, W. Lafayette, Indiana,47907
Source Phone Number:	765-494-8690
SIC Code:	8221
County Location:	Tippecanoe
Source Location Status:	Attainment for all criteria pollutants
Source Status:	Part 70 Permit Program (not yet issued) Major Source, under PSD Rules; Major Source, Section 112 of the Clean Air Act 1 of 28 Source Categories

A.2 Emission Units and Pollution Control Equipment Summary [326 IAC 2-7-4(c)(3)] [326 IAC 2-7-5(15)]

This stationary source consist of an existing ash silo for Boiler #5 with an existing wet ash loading system. This source is approved to construct and operate an additional dry ash loading system for Boiler #5 to load ash from the same ash silo with the following emission units and pollution control devices.

Dry Ash Loading System

The 300 ton per hour dry ash loading system for Boiler #5 air fluidizes ash to convey it from the ash silo then gravity feeds it into a truck through a telescoping spout with air displaced from the truck directed through a "filter module". The telescoping spout fits on top of the truck and contains the ash as it is gravity fed into the truck. The filter module has five canister filters #1 thru # 5 which exhaust to the atmosphere through a single vent, ASH 5C.

A.3 Part 70 Permit Applicability [326 IAC 2-7-2]

This stationary source is required to have a Part 70 permit by 326 IAC 2-7-2 (Applicability) because:

- (a) It is a major source, as defined in 326 IAC 2-7-1(22);
- (b) It is a source in a source category designated by the United States Environmental Protection Agency (U.S. EPA) under 40 CFR 70.3 (Part 70 - Applicability).

Permit Reviewer: Walter Habeeb

SECTION B GENERAL CONSTRUCTION CONDITIONS

B.1 Definitions [326 IAC 2-7-1]

Terms in this permit shall have the definition assigned to such terms in the referenced regulation. In the absence of definitions in the referenced regulation, the applicable definitions found in the statutes or regulations (IC 13-11, 326 IAC 1-2 and 326 IAC 2-7) shall prevail.

B.2 Effective Date of the Permit [IC13-15-5-3]

Pursuant to IC 13-15-5-3, this approval becomes effective upon its issuance.

B.3 Revocation of Permits [326 IAC 2-1.1-9(5)][326 IAC 2-7-10.5(i)]

Pursuant to 326 IAC 2-1.1-9(5)(Revocation of Permits), the Commissioner may revoke this approval if construction is not commenced within eighteen (18) months after receipt of this approval or if construction is suspended for a continuous period of one (1) year or more.

SECTION C GENERAL OPERATION CONDITIONS

C.1 Certification [326 IAC 2-7-4(f)][326 IAC 2-7-6(1)][326 IAC 2-7-5(3)(C)]

- (a) Where specifically designated by this permit or required by an applicable requirement, any application form, report, or compliance certification submitted shall contain certification by a responsible official of truth, accuracy, and completeness. This certification shall state that, based on information and belief formed after reasonable inquiry, the statements and information in the document are true, accurate, and complete.
- (b) One (1) certification shall be included, using the attached Certification Form, with each submittal requiring certification.
- (c) A responsible official is defined at 326 IAC 2-7-1(34).

C.2 Preventive Maintenance Plan [326 IAC 2-7-5(1),(3) and (13)] [326 IAC 2-7-6(1) and (6)] [326 IAC 1-6-3]

- (a) If required by specific condition(s) in Section D of this permit, the Permittee shall prepare and maintain Preventive Maintenance Plans (PMPs) when operation begins, including the following information on each facility:
 - (1) Identification of the individual(s) responsible for inspecting, maintaining, and repairing emission control devices;
 - (2) A description of the items or conditions that will be inspected and the inspection schedule for said items or conditions; and
 - (3) Identification and quantification of the replacement parts that will be maintained in inventory for quick replacement.

If, due to circumstances beyond the Permittee's control, the PMPs cannot be prepared and maintained within the above time frame, the Permittee may extend the date an additional ninety (90) days provided the Permittee notifies:

Indiana Department of Environmental Management
Compliance Branch, Office of Air Quality
100 North Senate Avenue, P. O. Box 6015
Indianapolis, Indiana 46206-6015

The PMP and the PMP extension notification do not require the certification by the "responsible official" as defined by 326 IAC 2-7-1(34).

- (b) The Permittee shall implement the PMPs as necessary to ensure that failure to implement a PMP does not cause or contribute to a violation of any limitation on emissions or potential to emit.
- (c) A copy of the PMPs shall be submitted to IDEM, OAQ, upon request and within a reasonable time, and shall be subject to review and approval by IDEM, OAQ, IDEM, OAQ, may require the Permittee to revise its PMPs whenever lack of proper maintenance causes or contributes to any violation. The PMP does not require the certification by the "responsible official" as defined by 326 IAC 2-7-1(34).
- (d) Records of preventive maintenance shall be retained for a period of at least five (5) years. These records shall be kept at the source location for a minimum of three (3) years. The records may be stored elsewhere for the remaining two (2) years as long as they are

available upon request. If the Commissioner makes a request for records to the Permittee, the Permittee shall furnish the records to the Commissioner within a reasonable time.

C.3 Permit Amendment or Modification [326 IAC 2-7-11] [326 IAC 2-7-12]

(a) Permit amendments and modifications are governed by the requirements of 326 IAC 2-7-11 or 326 IAC 2-7-12 whenever the Permittee seeks to amend or modify this permit.

(b) Any application requesting an amendment or modification of this permit shall be submitted to:

Indiana Department of Environmental Management
Permits Branch, Office of Air Quality
100 North Senate Avenue, P.O. Box 6015
Indianapolis, Indiana 46206-6015

Any such application shall be certified by the "responsible official" as defined by 326 IAC 2-7-1(34).

(c) The Permittee may implement administrative amendment changes addressed in the request for an administrative amendment immediately upon submittal of the request. [326 IAC 2-7-11(c)(3)]

C.4 Opacity [326 IAC 5-1]

Pursuant to 326 IAC 5-1-2 (Opacity Limitations), except as provided in 326 IAC 5-1-3 (Temporary Alternative Opacity Limitations), opacity shall meet the following, unless otherwise stated in this permit:

(a) Opacity shall not exceed an average of forty percent (40%) in any one (1) six (6) minute averaging period as determined in 326 IAC 5-1-4.

(b) Opacity shall not exceed sixty percent (60%) for more than a cumulative total of fifteen (15) minutes (sixty (60) readings as measured according to 40 CFR 60, Appendix A, Method 9 or fifteen (15) one (1) minute nonoverlapping integrated averages for a continuous opacity monitor) in a six (6) hour period.

C.5 Fugitive Dust Emissions [326 IAC 6-4]

The Permittee shall not allow fugitive dust to escape beyond the property line or boundaries of the property, right-of-way, or easement on which the source is located, in a manner that would violate 326 IAC 6-4 (Fugitive Dust Emissions).

C.6 Operation of Equipment [326 IAC 2-7-6(6)]

Except as otherwise provided by statute or rule, or in this permit, all air pollution control equipment listed in this permit and used to comply with an applicable requirement shall be operated at all times that the emission units vented to the control equipment are in operation.

C.7 Stack Height [326 IAC 1-7]

The Permittee shall comply with the applicable provisions of 326 IAC 1-7 (Stack Height Provisions), for all exhaust stacks through which a potential (before controls) of twenty-five (25) tons per year or more of particulate matter or sulfur dioxide is emitted by using good engineering practices (GEP) pursuant to 326 IAC 1-7-3.

Testing Requirements [326 IAC 2-7-6(1)]

C.8 Performance Testing [326 IAC 3-6][326 IAC 2-1.1-11]

- (a) Compliance testing on new emission units shall be conducted within 60 days after achieving maximum production rate, but no later than 180 days after initial start-up, if specified in Section D of this approval. All testing shall be performed according to the provisions of 326 IAC 3-6 (Source Sampling Procedures), except as provided elsewhere in this approval, utilizing any applicable procedures and analysis methods specified in 40 CFR 51, 40 CFR 60, 40 CFR 61, 40 CFR 63, 40 CFR 75, or other procedures approved by IDEM, OAQ.

A test protocol, except as provided elsewhere in this approval, shall be submitted to:

Indiana Department of Environmental Management
Compliance Data Section, Office of Air Quality
100 North Senate Avenue, P. O. Box 6015
Indianapolis, Indiana 46206-6015

no later than thirty-five (35) days prior to the intended test date. The protocol submitted by the Permittee does not require certification by the "responsible official" as defined by 326 IAC 2-7-1(34).

- (b) The Permittee shall notify IDEM, OAQ of the actual test date at least fourteen (14) days prior to the actual test date. The notification submitted by the Permittee does not require certification by the "responsible official" as defined by 326 IAC 2-7-1(34).
- (c) Pursuant to 326 IAC 3-6-4(b), all test reports must be received by IDEM, OAQ not later than forty-five (45) days after the completion of the testing. An extension may be granted by IDEM, OAQ, if the source submits to IDEM, OAQ, a reasonable written explanation not later than five (5) days prior to the end of the initial forty-five (45) day period.

Compliance Requirements [326 IAC 2-1.1-11]

C.9 Compliance Requirements [326 IAC 2-1.1-11]

The commissioner may require stack testing, monitoring, or reporting at any time to assure compliance with all applicable requirements. Any monitoring or testing shall be performed in accordance with 326 IAC 3 or other methods approved by the commissioner or the U. S. EPA.

Compliance Monitoring Requirements [326 IAC 2-7-5(1)] [326 IAC 2-7-6(1)]

C.10 Compliance Monitoring [326 IAC 2-7-5(3)] [326 IAC 2-7-6(1)]

If required by Section D, all monitoring and record keeping requirements shall be implemented when operation begins. The Permittee shall be responsible for installing any necessary equipment and initiating any required monitoring related to that equipment.

C.11 Monitoring Methods [326 IAC 3] [40 CFR 60] [40 CFR 63]

00012

Permit Reviewer: Walter Habeeb

Any monitoring or testing required by Section D of this permit shall be performed according to the provisions of 326 IAC 3, 40 CFR 60, Appendix A, 40 CFR 60 Appendix B, 40 CFR 63, or other approved methods as specified in this permit.

C.12 Pressure Gauge and Other Instrument Specifications [326 IAC 2-1.1-11] [326 IAC 2-8-4(3)] [326 IAC 2-8-5(1)]

- (a) Whenever a condition in this permit requires the measurement of pressure drop across any part of the unit or its control device, the gauge employed shall have a scale such that the expected normal reading shall be no less than twenty percent (20%) of full scale and be accurate within plus or minus two percent ($\pm 2\%$) of full scale reading.
- (b) Whenever a condition in this permit requires the measurement of a (temperature, flow rate, or pH level), the instrument employed shall have a scale such that the expected normal reading shall be no less than twenty percent (20%) of full scale and be accurate within plus or minus two percent ($\pm 2\%$) of full scale reading.
- (c) The Permittee may request the IDEM, OAQ approve the use of a pressure gauge or other instrument that does not meet the above specifications provided the Permittee can demonstrate an alternative pressure gauge or other instrument specification will adequately ensure compliance with permit conditions requiring the measurement of pressure drop or other parameters.

C.13 Compliance Response Plan - Preparation, Implementation, Records, and Reports[326 IAC 2-7-5] [326 IAC 2-7-6]

- (a) The Permittee is required to prepare a Compliance Response Plan (CRP) for each compliance monitoring condition of this permit. A CRP shall be submitted to IDEM, OAQ upon request. The CRP shall be prepared within ninety (90) days after issuance of this permit by the Permittee, supplemented from time to time by the Permittee, maintained on site, and comprised of:
 - (1) Reasonable response steps that may be implemented in the event that a response step is needed pursuant to the requirements of Section D of this permit; and an expected time frame for taking reasonable response steps.
 - (2) If, at any time, the Permittee takes reasonable response steps that are not set forth in the Permittee's current Compliance Response Plan and the Permittee documents such response in accordance with subsection (e) below, the Permittee shall amend its Compliance Response Plan to include such response steps taken.
- (b) For each compliance monitoring condition of this permit, reasonable response steps shall be taken when indicated by the provisions of that compliance monitoring condition as follows:
 - (1) Reasonable response steps shall be taken as set forth in the Permittee's current Compliance Response Plan; or
 - (2) If none of the reasonable response steps listed in the Compliance Response Plan is applicable or responsive to the excursion, the Permittee shall devise and implement additional response steps as expeditiously as practical. Taking such additional

00012

Permit Reviewer: Walter Habeeb

response steps shall not be considered a deviation from this permit so long as the Permittee documents such response steps in accordance with this condition.

- (3) If the Permittee determines that additional response steps would necessitate that the emissions unit or control device be shut down, the IDEM, OAQ shall be promptly notified of the expected date of the shut down, the status of the applicable compliance monitoring parameter with respect to normal, and the results of the actions taken up to the time of notification.
 - (4) Failure to take reasonable response steps shall constitute a violation of the permit.
- (c) The Permittee is not required to take any further response steps for any of the following reasons:
 - (1) A false reading occurs due to the malfunction of the monitoring equipment and prompt action was taken to correct the monitoring equipment.
 - (2) The Permittee has determined that the compliance monitoring parameters established in the permit conditions are technically inappropriate, has previously submitted a request for a minor permit modification to the permit, and such request has not been denied.
 - (3) An automatic measurement was taken when the process was not operating.
 - (4) The process has already returned or is returning to operating within "normal" parameters and no response steps are required.
- (d) When implementing reasonable steps in response to a compliance monitoring condition, if the Permittee determines that an exceedance of an emission limitation has occurred, the Permittee shall report such deviations pursuant to Section B-Deviations from Permit Requirements and Conditions.
- (e) The Permittee shall record all instances when response steps are taken. In the event of an emergency, the provisions of 326 IAC 2-7-16 (Emergency Provisions) requiring prompt corrective action to mitigate emissions shall prevail.
- (f) Except as otherwise provided by a rule or provided specifically in Section D, all monitoring as required in Section D shall be performed when the emission unit is operating, except for time necessary to perform quality assurance and maintenance activities.

C.14 Emergency Provisions [326 IAC 2-7-16]

- (a) An emergency, as defined in 326 IAC 2-7-1(12), is not an affirmative defense for an action brought for noncompliance with a federal or state health-based emission limitation.
- (b) An emergency, as defined in 326 IAC 2-7-1(12), constitutes an affirmative defense to an action brought for noncompliance with a technology-based emission limitation if the affirmative defense of an emergency is demonstrated through properly signed, contemporaneous operating logs or other relevant evidence that describe the following:

00012

Permit Reviewer: Walter Habeeb

- (1) An emergency occurred and the Permittee can, to the extent possible, identify the causes of the emergency;
- (2) The permitted facility was at the time being properly operated;
- (3) During the period of an emergency, the Permittee took all reasonable steps to minimize levels of emissions that exceeded the emission standards or other requirements in this permit;
- (4) For each emergency lasting one (1) hour or more, the Permittee notified IDEM, OAQ, within four (4) daytime business hours after the beginning of the emergency, or after the emergency was discovered or reasonably should have been discovered;

Telephone Number: 1-800-451-6027 (ask for Office of Air Quality,
Compliance Section), or
Telephone Number: 317-233-5674 (ask for Compliance Section)
Facsimile Number: 317-233-5967

- (5) For each emergency lasting one (1) hour or more, the Permittee submitted the attached Emergency Occurrence Report Form or its equivalent, either by mail or facsimile to:

Indiana Department of Environmental Management
Compliance Branch, Office of Air Quality
100 North Senate Avenue, P. O. Box 6015
Indianapolis, Indiana 46206-6015

within two (2) working days of the time when emission limitations were exceeded due to the emergency.

The notice fulfills the requirement of 326 IAC 2-7-5(3)(C)(ii) and must contain the following:

- (A) A description of the emergency;
- (B) Any steps taken to mitigate the emissions; and
- (C) Corrective actions taken.

The notification which shall be submitted by the Permittee does not require the certification by the "responsible official" as defined by 326 IAC 2-7-1(34).

- (6) The Permittee immediately took all reasonable steps to correct the emergency.
- (c) In any enforcement proceeding, the Permittee seeking to establish the occurrence of an emergency has the burden of proof.
 - (d) This emergency provision supersedes 326 IAC 1-6 (Malfunctions). This permit condition is in addition to any emergency or upset provision contained in any applicable requirement.

00012

Permit Reviewer: Walter Habeeb

- (e) IDEM, OAQ, may require that the Preventive Maintenance Plans required under 326 IAC 2-7-4-(c)(10) be revised in response to an emergency.
- (f) Failure to notify IDEM, OAQ, by telephone or facsimile of an emergency lasting more than one (1) hour in accordance with (b)(4) and (5) of this condition shall constitute a violation of 326 IAC 2-7 and any other applicable rules.
- (g) If the emergency situation causes a deviation from a technology-based limit, the Permittee may continue to operate the affected emitting facilities during the emergency provided the Permittee immediately takes all reasonable steps to correct the emergency and minimize emissions.

Corrective Actions and Response Steps [326 IAC 2-7-5] [326 IAC 2-7-6]

**C.15 Actions Related to Noncompliance Demonstrated by a Stack Test [326 IAC 2-7-5]
[326 IAC 2-7-6]**

- (a) When the results of a stack test performed in conformance with Section C - Performance Testing, of this permit exceed the level specified in any condition of this permit, the Permittee shall take appropriate response actions. The Permittee shall submit a description of these response actions to IDEM, OAQ, within thirty (30) days of receipt of the test results. The Permittee shall take appropriate action to minimize excess emissions from the affected facility while the response actions are being implemented.
- (b) A retest to demonstrate compliance shall be performed within one hundred twenty (120) days of receipt of the original test results. Should the Permittee demonstrate to IDEM, OAQ that retesting in one-hundred and twenty (120) days is not practicable, IDEM, OAQ may extend the retesting deadline.
- (c) IDEM, OAQ reserves the authority to take any actions allowed under law in response to noncompliant stack tests.

The documents submitted pursuant to this condition do require the certification by the "responsible official" as defined by 326 IAC 2-7-1(34).

Record Keeping and Reporting Requirements [326 IAC 2-7-5(3)] [326 IAC 2-7-19]

C.16 General Record Keeping Requirements [326 IAC 2-7-5(3)][326 IAC 2-7-6]

- (a) Records of all required data, reports and support information shall be retained for a period of at least five (5) years from the date of monitoring sample, measurement, report, or application. These records shall be kept at the source location for a minimum of three (3) years. The records may be stored elsewhere for the remaining two (2) years as long as they are available upon request. If the Commissioner makes a request for records to the Permittee, the Permittee shall furnish the records to the Commissioner within a reasonable time.
- (b) Unless otherwise specified in this permit, all record keeping requirements not already legally required shall be implemented within ninety (90) days of permit issuance.

C.17 General Reporting Requirements [326 IAC 2-7-5(3)(C)]

- (a) The reports required by conditions in Section D of this permit shall be submitted to:

00012

Permit Reviewer: Walter Habeeb

Indiana Department of Environmental Management
Compliance Data Section, Office of Air Quality
100 North Senate Avenue, P. O. Box 6015
Indianapolis, Indiana 46206-6015

- (b) Unless otherwise specified in this permit, any notice, report, or other submission required by this permit shall be considered timely if the date postmarked on the envelope or certified mail receipt, or affixed by the shipper on the private shipping receipt, is on or before the date it is due. If the document is submitted by any other means, it shall be considered timely if received by IDEM, OAQ, on or before the date it is due.
- (c) Unless otherwise specified in this permit, all reports required in Section D of this permit shall be submitted within thirty (30) days of the end of the reporting period. All reports do require the certification by the "responsible official" as defined by 326 IAC 2-7-1(34).
- (d) The first report shall cover the period commencing on the date of issuance of this permit and ending on the last day of the reporting period. Reporting periods are based on calendar years.

SECTION D.1

FACILITY OPERATION CONDITIONS

Facility Description [326 IAC 2-7-5(15)]

Dry Ash Loading System

The 300 ton per hour dry ash loading system for Boiler #5 air fluidizes ash to convey it from the ash silo then gravity feeds it into a truck through a telescoping spout with air displaced from the truck directed through a "filter module". The telescoping spout fits on top of the truck and contains the ash as it is gravity fed into the truck. The filter module has five canister filters #1 thru # 5 which exhaust to the atmosphere through a single vent, ASH 5C.

(The information describing the process contained in this facility description box is descriptive information and does not constitute enforceable conditions.)

Emission Limitations and Standards [326 IAC 2-7-5(1)]

D.1.1 Particulate Emissions Limitations 326 IAC 6-3-2(d)

Pursuant to 326 IAC 6-3-2(d) the particulate from the dry ash loading system, shall not exceed the pound per hour emission rate established as E in the following formula:

Interpolation and extrapolation of the data for the process weight rates up to sixty thousand (60,000) pounds per hour shall be accomplished by use of the equation:

$$E = 4.10 P^{0.67}$$

Interpolation and extrapolation of the data for the process weight rate in excess of sixty thousand (60,000) pounds per hour shall be accomplished by use of the equation:

$$E = 55.0 P^{0.11} - 40$$

where: E = rate of emission in lbs/hr;
P = process weight in tons/hr.
P = 300 TPH for this process

$$E = 63.0 \text{ lbs/hr}$$

D.1.2 Preventative Maintenance Plan [326 IAC 2-7-5(1)(13)]

A Preventative Maintenance Plan, in accordance with section C - Preventative Maintenance Plan, of this permit, is required for these facilities and their control devices.

D.1.3 Fugitive Dust Emissions [326 IAC 6-4]

Pursuant to 326 IAC 6-4 (Fugitive Dust Emissions), the Permittee shall not allow fugitive dust to escape beyond the property line or boundaries of the property, right-of-way, or easement on which the source is located.

D.1.4 326 IAC 5-1 (Opacity Limitations)

Pursuant to 326 IAC 5-1-2 (Opacity Limitations), except as provided in 326 IAC 5-1-3 (Temporary Alternative Opacity Limitations), opacity shall meet the following, unless otherwise stated in this permit:

00012

Permit Reviewer: Walter Habeeb

- (a) Opacity shall not exceed an average of forty percent (40%) any one (1) six (6) minute averaging period as determined in 326 IAC 5-1-4.
- (b) Opacity shall not exceed sixty percent (60%) for more than a cumulative total of fifteen (15) minutes (sixty (60) readings as measured according to 40 CFR 60, Appendix A, Method 9 or fifteen (15) one (1) minute nonoverlapping integrated averages for a continuous opacity monitor) in a six (6) hour period

Compliance Determination Requirements

D.1.5 Particulate Matter (PM)

- (a) The filter module and air filters for the dry ash loading system, for PM control, shall be in operation and control the PM emissions at all times that the dry ash loading system is in operation.

Compliance Monitoring Requirements [326 IAC 2-7-6(1)] [326 IAC 2-7-5(1)]

D.1.6 Visible Emissions Notations

- (a) Once per shift visible emission notations of the dust collector exhaust vent ASH 5C shall be performed during normal daylight operations and when the dry ash truck loading system is in operation. A trained employee shall record whether emissions are normal or abnormal.
- (b) Once per shift visible emission notations of the dry ash truck loading system shall be performed during normal daylight operations when the ash trucks are receiving ash. A trained employee shall record whether emissions are normal or abnormal.
- (c) For processes operated continuously, "normal" means those conditions prevailing, or expected to prevail, eighty percent (80%) of the time the process is in operation, not counting startup or shut down time.
- (d) In the case of batch or discontinuous operations, readings shall be taken during that part of the operation that would normally be expected to cause the greatest emissions.
- (e) A trained employee is an employee who has worked at the plant at least one (1) month and has been trained in the appearance and characteristics of normal visible emissions for that specific process.
- (f) The Compliance Response Plan for these units shall contain troubleshooting contingency and response steps for when an abnormal emission is observed. Failure to take response steps in accordance with Section C - Compliance Response Plan - Preparation, Implementation, Records, and Reports, shall be considered a violation of this permit.

D.1.7 Parametric Monitoring

The Permittee shall record the total static pressure drop across the air filters controlling emissions from the dry ash truck loading system, at least once per shift when the dry ash truck loading system is in operation. When for any one reading, the pressure drop across the air filter is outside the normal range of 1.0 and 7.0 inches of water or a range established during the latest stack test, the Permittee shall take reasonable response steps in accordance with Section C- Compliance Response Plan - Preparation, Implementation, Records, and Reports. A pressure reading that is outside the above mentioned range is not a deviation from this permit. Failure to take response

Permit Reviewer: Walter Habeeb

steps in accordance with Section C - Compliance Response Plan - Preparation, Implementation, Records, and Reports, shall be considered a violation of this permit.

The instrument used for determining the pressure shall comply with Section C - Pressure Gauge and Other Instrument Specifications, of this permit, shall be subject to approval by IDEM, OAQ, and shall be calibrated at least once every six (6) months.

Record Keeping and Reporting Requirement [326 IAC 2-7-5(3)] [326 IAC 2-7-19]

D.1.8 Record Keeping Requirements

To document compliance with Conditions D.1.6 and D.1.7, the Permittee shall maintain records in accordance with (i) through (ii) below. Records maintained for (i) through (ii) shall be taken daily when the dry ash truck loading system is in operation, unless otherwise specified below, and shall be complete and sufficient to establish compliance with the PM emissions limits established in Condition D.1.1.

- (i) Pressure drop (inlet/outlet differential static pressure) across the filter module;
- (ii) visible emissions observations shall be taken once per shift when the dry ash truck loading system is in operation.

All records shall be maintained in accordance with Section C - General Record Keeping Requirements, of this permit.

D.1.9 Reporting Requirements

There are no reporting requirements for this source.

INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT OFFICE OF AIR QUALITY

PART 70 SOURCE MODIFICATION CERTIFICATION

Source Name: Purdue University
Source Address: 423 S. Grant Street, West Lafayette, Indiana 47907
Mailing Address: 401 S. Grant Street, West Lafayette, Indiana 47907
Source Modification No.: 157-15996-00012

This certification shall be included when submitting monitoring, testing reports/results or other documents as required by this approval.

Please check what document is being certified:

- 9 Test Result (specify) _____
- 9 Report (specify) _____
- 9 Notification (specify) _____
- 9 Affidavit (specify) _____
- 9 Other (specify) _____

I certify that, based on information and belief formed after reasonable inquiry, the statements and information in the document are true, accurate, and complete.

Signature:

Printed Name:

00012

Permit Reviewer: Walter Habeeb

Title/Position:
Date:

February 17, 2003

**Indiana Department of Environmental Management
Office of Air Quality**

**Technical Support Document (TSD) for a Part 70 Minor Source
Modification.**

Source Background and Description

Source Name: Purdue University
Source Location: 423 South Grant Street, West Lafayette, Indiana 47907
Mailing Address: 401 S. Grant Street, 1665 L.J. Freehafer Hall of
Administrative Service. W. Lafayette, Indiana
47907
County: Tippecanoe
SIC Code: 8221
Operation Permit No.: T 157-7340-00012 (not issued yet)
Minor Source Modification No.: 157-15996-00012
Permit Reviewer: Walter Habeeb

The Office of Air Quality (OAQ) has reviewed an application from Purdue University relating to the construction of an additional ash loading system (a dry ash loading system) to the emission units and pollution control devices for their existing ash unloading system for Boiler # 5.

Dry Ash Loading System

The 300 ton per hour dry ash loading system for Boiler #5 air fluidizes ash to convey it from the ash silo then gravity feeds it into a truck through a telescoping spout with air displaced from the truck directed through a "filter module". The telescoping spout fits on top of the truck and contains the ash as it is gravity fed into the truck. The filter module has five canister filters #1 thru # 5 which exhaust to the atmosphere through a single vent, ASH 5C.

Enforcement Issue

There are no enforcement actions pending.

Stack Summary

Stack ID	Operation	Height (ft)	Dimension (in)	Flow Rate (acfm)	Temperature (°F)
ASH 5C	Boiler # 5	22	7 x 5.75	1000	Ambient

Recommendation

The staff recommends to the Commissioner that the Part 70 Minor Source Modification be approved. This recommendation is based on the following facts and conditions:

Unless otherwise stated, information used in this review was derived from the application and additional information submitted by the applicant.

An application for the purposes of this review was received on August 23, 2002, with additional information received on September 9, 2002, January 13, 2003 and February 10, 2003.

Emission Calculations

The calculations submitted by the applicant have been verified and found to be accurate and correct. These calculations are provided in Appendix A (page 1) of this document.

Potential To Emit of Modification

Pursuant to 326 IAC 2-1.1-1(16), Potential to Emit is defined as “the maximum capacity of a stationary source to emit any air pollutant under its physical and operational design. Any physical or operational limitation on the capacity of a source to emit an air pollutant, including air pollution control equipment and restrictions on hours of operation or type or amount of material combusted, stored, or processed shall be treated as part of its design if the limitation is enforceable by the U. S. EPA.”

This table reflects the PTE before controls. Control equipment is not considered federally enforceable until it has been required in a federally enforceable permit.

Pollutant	Potential To Emit (tons/year)
PM	6.91
PM-10	6.91
SO ₂	0.00
VOC	0.00
CO	0.00
NO _x	0.00

HAP's	Potential Emissions (tons/year)
Arsenic	0.01
Beryllium	0.00
Cadmium	0.00
Chromium	0.01
Formaldehyde	0.01
Glycol Ethers	0.00
Lead	0.01
Manganese	0.01
MEK	0.01
Methanol	0.00
Nickel	0.01
Toluene	0.01
TOTAL	0.08

All PM emissions are considered to be PM10.

Justification for Modification

The Part 70 Operating permit is being modified pursuant to Part 70 Permits: Source Modification

326 IAC 2-7-10.5(d)(4)(A). Modifications that would have the potential to emit within the following ranges, less than 25 TPY and equal to or greater than 5 TPY of either particulate matter (PM) or particulate matter less than ten (10) microns (PM 10).

County Attainment Status

The source is located in Tippecanoe County.

Pollutant	Status
PM-10	attainment
SO ₂	attainment
NO ₂	attainment
Ozone	attainment
CO	attainment
Lead	attainment

- (a) Tippecanoe County has been classified as attainment or unclassifiable for all criteria. Therefore, these emissions were reviewed pursuant to the requirements for Prevention of Significant Deterioration (PSD), 326 IAC 2-2 and 40 CFR 52.21.
- (b) Fugitive Emissions
Since this type of operation is one of the 28 listed source categories under 326 IAC 2-2 and since there are applicable New Source Performance Standards that were in effect on August 7, 1980, the fugitive PM emissions are counted toward determination of PSD and Emission Offset applicability.

Source Status

Existing Source PSD or Emission Offset Definition (emissions after controls, based upon 8760 hours of operation per year at rated capacity and/or as otherwise limited):

Pollutant	Emissions (tons/year)
PM	46
PM-10	46
SO ₂	3632
VOC	10
CO	273
NOx	653

- (a) This existing source is a major stationary source because an attainment regulated pollutant is emitted at a rate of 100 tons per year or more, and it is one of the 28 listed source categories.
- (b) These emissions are based upon 2000 OAQ emission data.

Potential to Emit of Modification After Issuance

The table below summarizes the potential to emit, reflecting all limits, of the significant emission units after controls. The control equipment is considered federally enforceable only after issuance of this Part 70 source modification.

	Potential to Emit (tons/year)						
Process/facility	PM	PM-10	SO ₂	VOC	CO	NO _x	HAPs
Ash Loading System for # 5 Boiler	0.022	0.022	0.0	0.0	0.0	0.0	0.0
PSD Significant Level	25	15	40	40	100	40	-

This modification to an existing major stationary source is not major because the emissions increase is less than the PSD significant levels. Therefore, pursuant to 326 IAC 2-2, and 40 CFR 52.21, the PSD requirements do not apply.

Federal Rule Applicability

- (a) There are no New Source Performance Standards (NSPS)(326 IAC 12 and 40 CFR Part 60) applicable to this proposed modification.
- (b) There are no National Emission Standards for Hazardous Air Pollutants (NESHAPs)(326 IAC 14 and 40 CFR Part 63) applicable to this proposed modification.

State Rule Applicability - Individual Facilities

Particulate 326 IAC 6-3-2(d)

Pursuant to 326 IAC 6-3-2(d), the particulate from the dry ash truck loading system shall not exceed the pound per hour emission rate established as E in the following formula:

Interpolation and extrapolation of the data for the process weight rates up to sixty thousand (60,000) pounds per hour shall be accomplished by use of the equation:

$$E = 4.10 P^{0.67}$$

Interpolation and extrapolation of the data for the process weight rates in excess of sixty thousand (60,000) pounds per hour shall be accomplished by use of the equation:

$$E = 55.0 P^{0.11} - 40$$

where E = rate of emission in pounds per hour and
P = process weight rate in tons/hour
P = 300 TPH for this process

$$E = 55.0 (300)^{0.11} - 40 = 63.0 \text{ lb/hr}$$

The filter module shall be used for dry ash truck loading system at all times the dry ash truck loading system is in operation, in order to comply with this limit.

326 IAC 6-4-2 (Fugitive dust emissions: emission limitations)

A source or source generating fugitive dust shall be in violation of this rule ((236 IAC 6-4) if any

of the following criteria are violated:

- (a) The ground level ambient air concentrations exceed fifty (50) micrograms per cubic meter above background concentrations for a sixty (60) minute period.
- (b) If fugitive dust is visible crossing the boundary or property line of a source.

326 IAC 5-1 (Opacity Limitations)

Pursuant to 326 IAC 5-1-2 (Opacity Limitations), except as provided in 326 IAC 5-1-3 (Temporary Alternative Opacity Limitations), opacity shall meet the following, unless otherwise stated in this permit:

- (a) Opacity shall not exceed an average of forty percent (40%) any one (1) six (6) minute averaging period as determined in 326 IAC 5-1-4.
- (b) Opacity shall not exceed sixty percent (60%) for more than a cumulative total of fifteen (15) minutes (sixty (60) readings as measured according to 40 CFR 60, Appendix A, Method 9 or fifteen (15) one (1) minute nonoverlapping integrated averages for a continuous opacity monitor) in a six (6) hour period.

Compliance Requirements

Permits issued under 326 IAC 2-7 are required to ensure that sources can demonstrate compliance with applicable state and federal rules on a more or less continuous basis. All state and federal rules contain compliance provisions, however, these provisions do not always fulfill the requirement for a more or less continuous demonstration. When this occurs IDEM, OAQ, in conjunction with the source, must develop specific conditions to satisfy 326 IAC 2-7-5. As a result, compliance requirements are divided into two sections: Compliance Determination Requirements and Compliance Monitoring Requirements.

Compliance Determination Requirements in Section D of the permit are those conditions that are found more or less directly within state and federal rules and the violation of which serves as grounds for enforcement action. If these conditions are not sufficient to demonstrate continuous compliance, they will be supplemented with Compliance Monitoring Requirements, also Section D of the permit. Unlike Compliance Determination Requirements, failure to meet Compliance Monitoring conditions would serve as a trigger for corrective actions and not grounds for enforcement action. However, a violation in relation to a compliance monitoring condition will arise through a source's failure to take the appropriate corrective actions within a specific time period.

The compliance monitoring requirements applicable to this modification are as follows:

1. The dry ash truck loading system has applicable compliance monitoring conditions as specified below:
 - (a) Visible emissions notations of exhaust vent ASH 5C for the dry ash truck loading system shall be performed once per shift during normal daylight operations when the dry ash truck loading system is in operation. A trained employee will record whether emissions are normal or abnormal. For processes operated continuously "normal" means those conditions prevailing, or expected to prevail, eighty percent (80%) of the time the process is in operation, not counting startup or shut down time. In the case of batch or discontinuous operations, readings shall be taken during that part of the operation that would normally be expected to cause the greatest emissions. A trained employee is an employee who has worked at the plant at least one (1) month and has been trained in the appearance and characteristics of normal visible emissions for that specific process. The

Preventive Maintenance Plan for this unit shall contain troubleshooting contingency and corrective actions for when an abnormal emission is observed.

- (b) The Permittee shall record the total static pressure drop across the air filters controlling the emissions from the dry ash truck loading system at least once per shift when the ash truck loading system is in operation. Unless operated under conditions for which the Preventive Maintenance Plan specifies otherwise, the pressure drop across the air filters shall be maintained within the range of 1.0 to 7.0 inches of water or a range established during the latest stack test. The Preventive Maintenance Plan for this unit shall contain troubleshooting contingency and corrective actions for when the pressure reading is outside of the above mentioned range for any one reading.

These monitoring conditions are necessary because the air filters for the dry ash truck loading system must operate properly to ensure compliance with 326 IAC 6-3-2 (Particulate Emission Limitations) and 326 IAC 2-7 (Part 70).

Conclusion

The construction of this proposed modification shall be subject to the conditions of the attached proposed Part 70 Minor Source Modification No. 157-15996-00012.

Appendix A

Company Name: Purdue University
Address City IN Zip: 423 S. Grant Street, W. Lafayette, In. 47907
County: Tippecanoe
Permit No.: 157-15996-00012
Permit Reviewer: Walter Habeeb
Date: September 16, 2002

PM/PM₁₀ Emissions From Ash Loading System For Boiler # 5

Dry Ash Truck Loading System*

Potential to Emit

System capacity - Maximum amount of ash from boiler (based on boiler capacity and coal ash content) is 51,179 TPY, maximum capacity of ash loading system is 300 TPH.

$$(51,179 \text{ tons/yr}) / (300 \text{ tons/hr}) = 170.6 \text{ hr/yr}$$
$$(0.27 \text{ lb/ton}) \times (300 \text{ ton/hr}) \times (170 \text{ hr/yr}) \times (1 \text{ ton}/2000\text{lb}) = 6.91 \text{ TPY}$$

Potential to Emit with Control

$$(0.03 \text{ gr/cf}) \times (1000 \text{ cf/min}) \times (60 \text{ min/hr}) \times (1 \text{ lb}/7000\text{gr}) = 0.26 \text{ lb/hr}$$
$$(0.26 \text{ lb/hr}) \times 170.6 \text{ hr/yr} \times (1 \text{ ton}/2000\text{lb}) = 0.022 \text{ TPY}$$

- * Filter module for truck loading fits on top of truck and allows ash to be unloaded into truck. Filters vent to stack (ASH5C). Manufacture information for filters, grain loading = 0.03 gr/cf, maximum flow rate = 1000 acfm through filters and maximum ash loading capacity = 300 tons per hour.
From AP-42, Table 11.12-2 Emission Factor - Pneumatic unloading of cement = 0.27 lb/ton
System capacity information provided by Purdue University